Table 23.2-2 Primary Road Drainage Structures

Road ID	Structure ID	Structure type	Watershed area (ac)	Length (ft)	Width or diameter (ft)	Design drawing	Hydrology and design data
East Haul Road	CP-406	Culvert	9.6	180	2.5	Exhibit 23.2-2	Appendix 23.B
East Haul Road	CP-407	Culvert	448.4	220	5.0	Exhibit 23.2-2	Appendix 23.B
East Haul Road	CP-408	Culvert	6.7	252	2.0	Exhibit 23.2-2	Appendix 23.B
East Haul Road	CP-409	Culvert	148.2	227	3.5	Exhibit 23.2-2	Appendix 23.B
East Haul Road	CP-410	Culvert	248.9	216	4.0	Exhibit 23.2-2	Appendix 23.B
East Haul Road	CP-411	Culvert	266.7	217	4.0	Exhibit 23.2-2	Appendix 23.B
East Haul Road	CP-412	Culvert	76.6	177	3.0	Exhibit 23.2-2	Appendix 23.B
East Haul Road	CP-413	Culvert	4.1	98	2.0	Exhibit 23.2-2	Appendix 23.B
East Haul Road	CP-414	Culvert	156.1	97	3.0	Exhibit 23.2-2	Appendix 23.B
East Haul Road	EHR-RD1	Relief ditch	3.0	30	4.0	Exhibit 23.2-2	Appendix 23.C
East Haul Road	EHR-RD2	Relief ditch	0.3	52	4.0	Exhibit 23.2-2	Appendix 23.C
East Haul Road	EHR-RD3	Relief ditch	2.2	48	4.0	Exhibit 23.2-2	Appendix 23.C
East Haul Road	EHR-RD4	Relief ditch	0.4	26	4.0	Exhibit 23.2-2	Appendix 23.C
East Haul Road	EHR-RD5	Relief ditch	0.5	32	4.0	Exhibit 23.2-2	Appendix 23.C
East Haul Road	EHR-CB1	Relief ditch	4.0	10	10	Exhibit 23.2-2	Appendix 23.C
East Haul Road	EHR-CB2	Relief ditch	4.6	10	10	Exhibit 23.2-2	Appendix 23.C
East Haul Road	EHR-RD6	Relief ditch	0.9	30	4.0	Exhibit 23.2-2	Appendix 23.C
East Haul Road	SRL-RD7	Relief ditch	0.7	32	4.0	Exhibit 23.2-2	Appendix 23.C
East Haul Road	SRL-RD8	Relief ditch	1.4	30	4.0	Exhibit 23.2-2	Appendix 23.C
East Haul Road	SRL-RD9	Relief ditch	3.2	100	4.0	Exhibit 23.2-2	Appendix 23.C

RD = Relief Ditch
CP = Culvert

Field Code Changed